



Precast Lift Slab - Block D4									
Bar Mark	Type and size	Total No.	Length of each bar	Shape code	A'mm	B'mm	C'mm	D'mm	Total Weight (kg)
Block D4 - Precast Lift Cover A									
01	H16	21	2100	00	2100	0	0	0	70
02	H12	21	2100	00	2100	0	0	0	39
03	H20	8	400	00	400	0	0	0	8
04	H16	16	2800	00	2800	0	0	0	71
05	H12	16	2800	00	2800	0	0	0	40
06	H16	74	1450	21	700	110	700	0	169
									312
Block D4 - Precast Lift Cover B									
01	H16	21	2100	00	2100	0	0	0	70
02	H12	21	2100	00	2100	0	0	0	39
03	H20	8	400	00	400	0	0	0	8
04	H16	16	2800	00	2800	0	0	0	71
05	H12	16	2800	00	2800	0	0	0	40
06	H16	74	1450	21	700	110	700	0	169
									793

Weight - Precast Lift Cover (Block D4)	
Mark	Weight
Block D4 - Precast Lift Cover A	3469 kg
Block D4 - Precast Lift Cover B	3479 kg

- Notes:
- Do not scale from this drawing. Use figure dimensions only.
  - This drawing is to be read in conjunction with all related Architects, Consultants & Sub-Contractors drawings and specifications.
  - The contractor is advised that all design drawings and information are to be read concurrently and any discrepancies or omissions reported directly to Simtrical Structural Department.
  - The contents of this drawing may not be reproduced in whole or in part without the prior written permission of Simtrical Ltd.



Rev	First Issue	Description	SP	02.04.19	SC
P01	First Issue		SP	02.04.19	SC

**SIMTRICAL**  
a more dynamic view

3 Horizon Place, Studio Way  
Borehamwood  
Hertfordshire, WD6 5FP

T: +44 (0) 7404 134 433  
W: www.simtrical.co.uk  
E: office@simtrical.co.uk

Client Details:  
Berkeley Homes Ltd.

Project Details:  
Kidbrooke Village - Phase 3 Block D

Drawing Title:  
RC Details - Precast Lift Capping Slabs - Block D4

Scale	Date	Drawn By	Checked By	Approved By
As indicated	Mar '19	SP	SP	SP

Status:  
Preliminary

Drawing Number	Revision
P16141L-GCL-D4-XX-DR-S-DET-31300	P01